

# FLAT MDB W/ HOME RUN

## 15M 6MM<sup>2</sup> 6-WAY

6 circuit 6 port outlet boxes with 19 core 6.0mm<sup>2</sup> Home Run cables. The Home Run cable has a gland and locknut to fix to the Distribution Board header trunking and 3m tails for on site wiring. The length of the home run will vary dependant on its position within the building.

NUMBER OF CORES	18 + E
POWER DIAMETER	18 x 6.0mm <sup>2</sup> L, N, E + 1 x 4.0mm <sup>2</sup> CPC
RATED CURRENT (A)	32 A (max)
RATED IMPULSE VOLTAGE	4 kV
POWER OUTPUTS	3 Pin (6 Ports)
RATED VOLTAGE	250/400 V

FREQUENCY (HZ)	50 Hz
MECHANICAL CODING	Code 1 (Blue)
LOCKABLE	Self-locking (unlocking by disconnect tool)
DEGREE OF PROTECTION (IP)	IP20 (disconnected), IP40 (connected)
CONNECTOR STANDARD	IEC61535:2009+A1:2013 QMS: ISO9001:2016
WIRING AND TEST STANDARD	BS8488:2009+A1:2010
TOTAL WEIGHT	29.66Kg
TOTAL CO2e (kg/CO2e)	116.02Kg

### DIMENSIONS

