

FLAT MDB W/ HOME RUN

35M 6MM² 6-WAY

6 circuit 6 port outlet boxes with 19 core 6.0mm² Home Run cables. The Home Run cable has a gland and locknut to fix to the Distribution Board header trunking and 3m tails for on site wiring. The length of the home run will vary dependant on its position within the building.

| | |
|-----------------------|--|
| NUMBER OF CORES | 18 + E |
| POWER DIAMETER | 18 x 6.0mm ² L, N, E + 1 x 4.0mm ² CPC |
| RATED CURRENT (A) | 32 A (max) |
| RATED IMPULSE VOLTAGE | 4 kV |
| POWER OUTPUTS | 3 Pin (6 Ports) |
| RATED VOLTAGE | 250/400 V |

| | |
|---------------------------|---|
| FREQUENCY (HZ) | 50 Hz |
| MECHANICAL CODING | Code 1 (Blue) |
| LOCKABLE | Self-locking (unlocking by disconnect tool) |
| DEGREE OF PROTECTION (IP) | IP20 (disconnected), IP40 (connected) |
| CONNECTOR STANDARD | IEC61535:2009+A1:2013 QMS: ISO9001:2016 |
| WIRING AND TEST STANDARD | BS8488:2009+A1:2010 |
| TOTAL WEIGHT | 68.29Kg |
| TOTAL CO2e (kg/CO2e) | 267.15Kg |

DIMENSIONS

