

# FLAT MDB W/ HOME RUN

## 45M 6MM<sup>2</sup> 6-WAY

6 circuit 6 port outlet boxes with 19 core 6.0mm<sup>2</sup> Home Run cables. The Home Run cable has a gland and locknut to fix to the Distribution Board header trunking and 3m tails for on site wiring. The length of the home run will vary dependant on its position within the building.

|                       |  |
|-----------------------|--|
| NUMBER OF CORES       | 18 + E   |
| POWER DIAMETER        | 18 x 6.0mm <sup>2</sup> L, N, E + 1 x 4.0mm <sup>2</sup> CPC |
| RATED CURRENT (A)     | 32 A (max)   |
| RATED IMPULSE VOLTAGE | 4 kV   |
| POWER OUTPUTS         | 3 Pin (6 Ports)  |
| RATED VOLTAGE         | 250/400 V  |

|                           |   |
|---------------------------|---|
| FREQUENCY (HZ)            | 50 Hz                                       |
| MECHANICAL CODING         | Code 1 (Blue)                               |
| LOCKABLE                  | Self-locking (unlocking by disconnect tool) |
| DEGREE OF PROTECTION (IP) | IP20 (disconnected), IP40 (connected)       |
| CONNECTOR STANDARD        | IEC 61535:2009+A1:2013<br>QMS: ISO9001:2016 |
| WIRING AND TEST STANDARD  | BS8488:2009+A1:2010                         |
| TOTAL WEIGHT              | 87.61Kg                                     |
| TOTAL CO2e (kg/CO2e)      | 342.71Kg                                    |

DIMENSIONS

